




OPENING HEIGHT	VERTICAL HEADROOM	HORIZONTAL HEADROOM
THRU 8'-0"	18"	17 1/2"
OVER 8'-0" THRU 10'-0"	18 1/2"	17 3/4"
OVER 10'-0" THRU 12'-0"	18 3/4"	18"
OVER 12'-0" THRU 14'-0"	19"	18 1/2"

1. OPERATION TYPE MAY BE PUSH-UP, RIGHT HAND CHAIN HOIST, OR RIGHT HAND INTERNAL ELECTRIC.
2. FOR CRITICAL FITS DUE TO REDUCED AVAILABLE HEADROOM OR SIDEROOM CLEARANCES, CONSULT FACTORY.
3. CLEARANCES SHOWN ARE MAXIMUMS. LESSER CLEARANCES MAY BE POSSIBLE.
4. UNLESS OTHERWISE NOTED, DOORS SHALL BE PROVIDED WITH SLIDE LOCKS AT EACH END OF BOTTOM BAR, ENGAGING GUIDES IN THE LOCKED POSITION (OPTIONAL CURTAIN MOUNTED MINI LATCH)
5. ALL OPENING PREPARATION, ELECTRICAL POWER AND FIELD PAINTING SHALL BE PROVIDED BY OTHERS.
6. SERIES 1000I IS AN INSULATED SERIES 1000.
7. CURTAIN FINISH SHALL BE SILICONE POLYESTER PRE-PAINT OVER GALVANIZED GRADE 80 STEEL.
8. GUIDES, BRACKETS, BOTTOM BAR ANGLE AND HEAD STOPS ARE ZINC COATED.
9. MAXIMUM OPENING SIZE: 12'-0" X 14'-0"
10. RAIN LIP CLEARANCE DIMENSION OUTSIDE OF GUIDE = 4-1/2" MINIMUM
11. 36" MAX HOLE SPACING.



(*) FOR PUSH-UP OPERATION.....4"
 FOR HAND CHAIN OPERATION.....4"
 FOR ELECTRIC OPERATION.....4"
 FOR OUTSIDE OF CHAIN DRIVE.....6"
 FOR ATA OPERATION.....6 ³/₄"
 NOTE: RIGHT SIDE DRIVE SHOWN



16 GA GUIDE MOUNTING DETAIL

L.E. 10/11/2024

CUSTOMER NUMBER:		DATE:	
CUSTOMER NAME:		CONTACT:	
PROJECT NAME:			
PROJECT LOCATION:			
PLANT:		SALESPERSON:	
DRAWN BY:	DATE:	Austin Building Systems Call 888-399-6079 buildmetal.com	
DRAWING NUMBER:	SHT: OF:		

[illegible]